

CEDIA
BEST NEW
PRODUCT
WINNER



Dual Valve Automatic Water Shut-Off System

A more efficient way to control water shut-offs in homes with two incoming water lines.

Perfect for condominiums, apartments, villas, attached homes, and commercial breakroom pantries using multiple line water feeds. Shut-off valves open/close simultaneously when notified by sensors, alarm panel or compatible SmartConnect WiFi device and app.

WaterCop® Pro Dual Valve System

This system provides the most complete plumbing leak protection while offering the most flexible installation options and third-party monitoring/security integration or SmartConnect device and mobile app.



The proven leader in household leak protection:

is there when you're not.

Provides leak protection for homes with two incoming water lines.

WaterCop® Pro Dual Valve System



Ordering Information

Step One: Select shut-off valve #1 by size

Step Two: Select shut-off valve #2 by size

SIZE (FNPT)	PART NO. (LEAD FREE NSF/ANSI 372)
1/2"	WCVLF 1/2
3/4"	WCVLF 3/4
1"	WCVLF 1
1 1/4"	WCVLF 1 1/4

Step Three: Select correct WaterCop® Pro Dual Kit

PART NO.	DESCRIPTION
WPK25D	CONTROL PANEL/(2) 25' PLENUM CABLES/ (2) PRO INTEGRATED ACTUATORS
WPK50D	CONTROL PANEL/(2) 50' PLENUM CABLES/ (2) PRO INTEGRATED ACTUATORS
WPK75D	CONTROL PANEL/(2) 75' PLENUM CABLES/ (2) PRO INTEGRATED ACTUATORS
WPKH25D	CONTROL PANEL WITH HW INPUTS/(2) 25' PLENUM CABLES/ (2) PRO INTEGRATED ACTUATORS
WPKH50D	CONTROL PANEL WITH HW INPUTS/(2) 50' PLENUM CABLES/ (2) PRO INTEGRATED ACTUATORS
WPKH75D	CONTROL PANEL WITH HW INPUTS/(2) 75' PLENUM CABLES/ (2) PRO INTEGRATED ACTUATORS



Features

- NSF/ANSI 372* approved lead-free brass, full flow, 600 psi rated industrial valve
- Sizes 1/2" – 1 1/4" standard (1 1/2" to 4" large valve integration available)
- Wireless sensors
- Single or dual wireless leak, rope and pressure sensors available
- Fully supervised and addressable sensors alert upon water detection, power lost, low battery, and sensor short/open
- 10' white sensor cord with corrosion-resistant gold-plated prongs
- Multisense hub supports up to 45 wireless leak sensors (90 point detection) or 8 hardwired sensors per control panel
- Wireless sensor signal can be enhanced for longer distances (Part No. WPR)
- Local open/close water control
- Can be used for above grade or below grade
- Connection cable is not direct burial rated

* Lead Free NSF/ANSI 372 refers to the wetted surface of pipe, fitting and fixtures in potable water systems that have a weighted average lead content ≤ 0.25%. Source: California Health & Safety Code (116875); Vermont Act 193.

Step Four: Select accessories

PART NO.	DESCRIPTION
WPM	WATERCOP MULTISENSE HUB
WPSC	WATERCOP PRO LEAK SENSOR 10' CABLE AND PROBE
WPRS095	WATERCOP PRO PRESSURE SENSOR 95 PSI MAX 1/4" NPT
WROPE6	WATERCOP PRO 6' ROPE SENSOR WITH PLUG, INCLUDES 20 CLIPS
WSPLIT	WATERCOP PRO AUXILIARY SPLITTER FOR MULTISENSE HUB
WEXT6	WATERCOP PRO AUXILIARY 6' EXTENSION
WCSG	WATERCOP SENSOR GUARD
ACA100	WATERCOP PRO AC ADAPTER FOR LOW VOLTAGE MULTISENSE HUB
RS100	WATER CONTROL WALL SWITCH (CABLE NOT INCLUDED)
WCSCLV	WATERCOP SMART CONNECT – WIFI + MOBILE APP INTERFACE
WPR	WATERCOP PRO RANGE ENHANCING SENSOR REPEATER

SmartConnect

Receive mobile alerts and control your WaterCop system using the WaterCop app on a phone or tablet. SmartConnect is compatible with Classic, Pro and LeakStop+ systems.

- 24/7 remote mobile control and access to your WaterCop system
- WiFi compatible
- Mobile alerts about power outages



To order or for additional information, visit

or call 800-545-3636.